

Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 1 of 5

TEST REPORT

for

Palziv North America 7966 NC 56 Hwy Louisburg, NC 27549

Impact Sound Transmission Test

ASTM E 492 – 09 / ASTM E 989 – 06

On

6 Inch Concrete Slab Floor – Suspended Ceiling Assembly Overlaid with; Engineered Wood Flooring on ECO Cork Foam Underlayment

Report Number: NGC 7014130

Assignment Number: G-1048

Test Date: 6/9/2014

Report Approval Date: 7/10/2014

Submitted by:

Andrew E. Heuer Senior Test Engineer

Reviewed by:

Robert J. Menchett Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

NGC 7014130 Palziv North America 7/10/2014 Page 2 of 5

Revision Summary:

Date	SUMMARY		
Approval Date: 7/10/2014	Original issue date. Original NGCTS report: NGC 7014130		

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

1650 Military Road • Buffalo, NY 14217-1198 (716) 873-9750 • Fax (716) 873-9753 • www.ngctestingservices.com



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Report Number: NGC 7014130

Page 3 of 5

Test Method: This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine -Designation: E 492-09/ E 989-06.

The uncertainty limits of each tapping machine location met the precision requirements of section A1.4 of ASTM E 492-09.

Specimen Description: 6 inch concrete slab floor-suspended ceiling assembly overlaid with, according to client, Engineered Wood Flooring on ECO Cork Foam underlayment.

The test specimen was a floor- suspended ceiling assembly observed to consist of the following. All measured weights and dimensions are averaged:

- 1 layer of, according to client, Engineered Wood Flooring. The engineered wood flooring was floating on the underlayment. Observed dimensions: Random length planks
 Measured thickness: 9.63 mm (0.379 in.) Measured weight: 6.69 kg/m² (1.37 PSF)
- 1 layer of, according to the client, ECO Cork Foam underlayment. The underlayment seams were butted and taped together, and was floating over the concrete slab. Measured thickness: 3.25 mm (0.1280 in.) Measured weight: 0.40 kg/m² (0.08 PSF)
- 152.4 mm (6 in.) thick reinforced concrete slab, weighing: 366.2 kg/m² (75.0 PSF)
- 1 layer of, 88.9 mm (3.5 in.) unfaced fiberglass batt insulation which was laid over the suspended grid system/ parallel to the main tees. Sample weight: 0.78 kg/m² (0.16 PSF)
- Gypsum wallboard ceiling grid suspension system. System is comprised of main tees and cross tees. The main tees were placed 1219.2 mm (48 in.) o.c. and the cross tees were placed 609.6 mm (24 in.) o.c.
 16 gauge galvanized tie wire was used to attach the main tees to concrete anchors, located 1219.2 mm (48 in.) o.c. along the longitudinal axis, suspending the grid 304.8 mm (12 in.) below the concrete slab.
- 1 layer of, 15.9 mm (5/8 in.) Type X gypsum wallboard. The wallboard was attached parallel to the suspended grid suspension system mains, using 28.6 mm (1-1/8 in.) Type S drywall screws spaced 304.8 mm (12 in.) o.c. The wallboard joints were taped. Suspended gypsum wallboard grid ceiling weighted: 11.23 kg/m² (2.3 PSF)

The overall weight of the test assembly: 385.24 kg/m² (78.91 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough. The test frame was structurally isolated from the receiving room.

Specimen size:3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)Conditioning:Concrete slab cured for a minimum of 28 days.Test Results:The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

1650 Military Road • Buffalo, NY 14217-1198 (716) 873-9750 • Fax (716) 873-9753 • www.ngctestingservices.com



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Test Report: NGC7014130 Specimen Size [m²]: 17.8			Page 4 of Date: 6/9/2014			
Source room Rm Temp [°C]: 21.5 Humidity [%]: 63			Receiving room Volume [m³]: 60.5 Rm Temp [°C]: 21.5 Humidity [%]: 63			
mpact Insulatio		[dB]:	73			
Sum of Unfavorable D		25				
Max. Unfavorable Dev	and a second	8	at	125	Hz	
Frequency	Ln	L2	d	Corr.	u.Dev.	ΔL _n
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
100	45	47.9	33.5	-2.9	6	2.19
125	47	52.1	21.4	-5.1	8	2.63
160	47	52.5	16.6	-5.5	8	2.78
200	40	46.3	15.5	-6.3	1	0.87
250	41	46.6	17.1	-5.6	2	0.44
315	38	43.8	17.0	-5.8		0.70
400	35	42.0	16.7	-7.0		0.49
500	32	38.8	18.3	-6.8		0.28
630	31	37.6	20.0	-6.6		0.35
800	26	31.9	20.3	-5.9		0.16
1000	26	30.1	22.1	-4.1		0.14
1250	22	25.7	24.4	-3.7		0.19
1600	12	18.0	25.6	-6.0		0.18
2000	17	20.7	29.6	-3.7		0.27
2500	13	17.6	32.2	-4.6		0.08
3150	11	15.8	33.8	-4.8		0.15
				200 EV		the second s
5000	7	11.1	42.2	-4.1		0.22
3150 4000 5000	11 9 7	$ \begin{array}{c c} & 13.3 \\ & 11.1 \\ & L_n &= Na \\ & L2 &= R \\ & d &= D \end{array} $	37.6 42.2 ormalized S eceiving Ro ecay Time,	-4.3 -4.1 ound Pres om Level, dB/second		0.15

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.




ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL



Laboratory

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.

1650 Military Road • Buffalo, NY 14217-1198 (716) 873-9750 • Fax (716) 873-9753 • www.ngctestingservices.com